APPENDIX B

PARTIES OF INTEREST

APPENDIX B
PARTIES OF INTEREST
Chippewa Sand Company
Chippewa County, Wisconsin

OWNER NAME	CONTACT ADDRESS	PIN GIS	SITE ADRESS (WHEN APPLICABLE)
	18441 COUNTY HWY DD, BLOOMER WI, 54724	23010-0543-00000000	
CHRIS & DENNIS CULVER & CULVER	1303 178TH AVE, BLOOMER WI, 54724	23010-0812-00000000	17787 COUNTY HWY DD
CHRIS & DENNIS CULVER & CULVER	1303 178TH AVE, BLOOMER WI, 54724	23010-0813-00000000	
THOMAS J & ANTHONY J SHORT & PECHA	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-0842-00000000	
ROBERT W & DORIS E MERTENS & DURST	18069 54TH AVE, CHIPPEWA FALLS WI, 54729	23010-0233-00020000	
DONALD W & LISA A PRILL	4121 186TH AVE, BLOOMER WI, 54724	23010-0333-00000000	
JAMES G & CLAUDIA J SPRINGER	16569 STATE HWY 40, BLOOMER WI, 54724	23010-0334-00020000	
SAMUEL R & WENDY M LAGESSE	4621 186TH AVE, BLOOMER WI, 54724	23010-0343-00020000	
JAMES G & CLAUDIA J SPRINGER	16569 STATE HWY 40, BLOOMER WI, 54724	23010-0343-04000000	
%ROSEMARY GEHRING GEHRING & ARENDT, T	1403 15TH AVE APT 202, BLOOMER WI, 54724	23010-0344-00020000	
CHAD D & BARBARA J ARENDT	18210 50TH ST, BLOOMER WI, 54724	23010-0344-70784001	18210 50TH ST
JEFF & CINDY MICHAELIS	18200 50TH ST, BLOOMER WI, 54724	23010-0344-70784002	18200 50TH ST
%WAYNE & JUDITH ROGGE W & J R #2 LLC	707 W TARR RD, NEW AUBURN WI, 547578547	23010-0433-00000000	
%KEVIN ROGGE TR & KR LLC	16551 COUNTY HWY F, BLOOMER WI, 54724	23010-0434-00000000	
CAROL & ALLEN PAULSON TRUST & PFE	19022 75TH AVE, CHIPPEWA FALLS WI, 547298276	23010-0443-00000000	
CAROL & ALLEN PAULSON TRUST & PFE	19022 75TH AVE, CHIPPEWA FALLS WI, 547298276	23010-0444-00000000	
DARREL W & MARY J FEHR	18441 COUNTY HWY DD, BLOOMER WI, 54724	23010-0544-00000000	
THOMAS J & ANTHONY J SHORT & PECHA	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-0841-00000000	
THOMAS J & ANTHONY J SHORT & PECHA	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-0844-00000000	2968 COUNTY HWY A
LUKE M BUCHNER	3120 COUNTY HWY A, BLOOMER WI, 54724	23010-0933-06000000	3120 COUNTY HWY A
JOHN D IV & JESSICA R SYKORA	3594 COUNTY HWY A, BLOOMER WI, 54724	23010-0943-05010000	3594 COUNTY HWY A
TODD J & VICKI L BUCHNER	3834 COUNTY HWY A, BLOOMER WI, 54724	23010-0944-06000000	3834 COUNTY HWY A
PROPERTIES LLC MARIE ANDERSON	1165 22ND ST, CHETEK WI, 54728	23010-1013-00000000	
PROPERTIES LLC MARIE ANDERSON	1165 22ND ST, CHETEK WI, 54728	23010-1014-00020000	17538 50TH ST
TRAVIS D & ALEXIS J TUMA	10678 24TH AVE, EAU CLAIRE WI, 54703	23010-1014-72699001	
SCOTT T KRENZ	4152 COUNTY HWY A, BLOOMER WI, 54724	23010-1033-08250000	4152 COUNTY HWY A
LIMITED PARTNERSHIP WISCONSIN ROBINSON	2725 W HIGHLAND BLVD, SUITE 219, MILWAUKEE WI, 53208	23010-1034-72027001	4364 COUNTY HWY A
STANLEY D SARAUER	17273 50TH ST, BLOOMER WI, 54724	23010-1041-00000000	
GLENN R SARAUER	4993 COUNTY HWY A, BLOOMER WI, 54724	23010-1043-00000000	
STANLEY D SARAUER	17273 50TH ST, BLOOMER WI, 54724	23010-1044-00000000	
GERALD N & RENEE A HARMS	17793 50TH ST, BLOOMER WI, 54724	23010-1122-00210000	
GERALD N & RENEE A HARMS	17793 50TH ST, BLOOMER WI, 54724	23010-1122-05010000	17793 50TH ST
COREY B & EMILY E SHEPLEE	2477 19TH AVE, RICE LAKE WI, 54868	23010-1123-72849001	
COREY B & EMILY E SHEPLEE	2477 19TH AVE, RICE LAKE WI, 54868	23010-1123-72850008	
CHRISTOPHER S & ANDREA B CAGLE	17687 50TH ST, BLOOMER WI, 54724	23010-1123-73825009	17687 50TH ST
GLENN R SARAUER	4993 COUNTY HWY A, BLOOMER WI, 54724	23010-1512-00020000	
FT BUSINESS LLC	4041 COUNTY HWY A, BLOOMER WI, 54724	23010-1521-00020000	4497 COUNTY HWY A
JEREMY R & JAMIE NELSON	4367 COUNTY HWY A, BLOOMER WI, 54724	23010-1521-02250000	4367 COUNTY HWY A
RICHARD L & VIRGINIA J SCHINDLER	4263 COUNTY HWY A, BLOOMER WI, 54724	23010-1521-73178001	4263 COUNTY HWY A
FT BUSINESS LLC	4041 COUNTY HWY A, BLOOMER WI, 54724	23010-1522-00020000	4041 COUNTY HWY A
GEORGIANN L SCRITSMIER TRUST	4644 E CHCHISE DR, PHOENIX AZ, 850284219	23010-1522-03750000	
JEROME L SCRITSMIER TRUST	2454 N CAMERON AVE, COVINA CA, 91724	23010-1522-04250000	
TRAVIS H & ANGELA L WAGNER	16919 40TH ST, BLOOMER WI, 54724	23010-1522-05250000	16919 40TH ST
ANTHONY J & THOMAS J PECHA & SHORT	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-1611-00020000	
ROY A & GEORGIA J BUCHNER TRUST	2713 28 3/8TH ST, BIRCHWOOD WI, 54817	23010-1611-73461001	16972 40TH ST
ROY A & GEORGIA J BUCHNER TRUST	2713 28 3/8TH ST, BIRCHWOOD WI, 54817	23010-1611-73461002	3909 COUNTY HWY A
VICTORIA D TRINKO	3717 COUNTY HWY A, BLOOMER WI, 54724	23010-1611-73461003	
VICTORIA D TRINKO	3717 COUNTY HWY A, BLOOMER WI, 54724	23010-1612-00000000	3717 COUNTY HWY A
ANTHONY J & THOMAS J PECHA & SHORT	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-1621-00000000	
ANTHONY J & THOMAS J PECHA & SHORT	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-1622-00020000	
ANTHONY J & THOMAS J PECHA & SHORT	16595 COUNTY HWY DD, BLOOMER WI, 54724	23010-1622-02000000	

APPENDIX C

NRCS WEB SOIL SURVEY CUSTOM SOIL RESOURCES REPORT

United States Department of Agriculture

NRCS

Natural Resources Conservation Service

A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Chippewa County, Wisconsin



November 28, 2017

Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report
Soil Map

Map Scale: 1:11,700 if printed on B landscape (17" x 11") sheet.

N

Meters
0 150 300 600 900

Feet
0 500 1000 2000 3000

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 15N WGS84

MAP LEGEND

Area of Interest (AOI)
- Area of Interest (AOI)

Soils
- Soil Map Unit Polygons
- Soil Map Unit Lines
- Soil Map Unit Points

Special Point Features
- Blowout
- Borrow Pit
- Clay Spot
- Closed Depression
- Gravel Pit
- Gravelly Spot
- Landfill
- Lava Flow
- Marsh or swamp
- Mine or Quarry
- Miscellaneous Water
- Perennial Water
- Rock Outcrop
- Saline Spot
- Sandy Spot
- Severely Eroded Spot
- Sinkhole
- Slide or Slip
- Sodic Spot
- Spoil Area
- Stony Spot
- Very Stony Spot
- Wet Spot
- Other
- Special Line Features

Water Features
- Streams and Canals

Transportation
- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

Background
- Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Chippewa County, Wisconsin
Survey Area Data: Version 13, Oct 5, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 19, 2013—Mar 7, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AlC	Amery sandy loam, 6 to 12 percent slopes	5.9	0.5%
AoA	Arenzville silt loam, 0 to 3 percent slopes, occasionally flooded	2.0	0.2%
ApB	Arland sandy loam, 2 to 6 percent slopes	29.9	2.8%
ApC2	Arland sandy loam, 6 to 12 percent slopes, eroded	15.6	1.4%
ApD2	Arland sandy loam, 12 to 20 percent slopes, eroded	21.3	2.0%
AsB	Arland loam, 2 to 6 percent slopes	3.5	0.3%
BlB	Billett sandy loam, 2 to 6 percent slopes	45.1	4.2%
BlC2	Billett sandy loam, 6 to 12 percent slopes, eroded	3.9	0.4%
BmA	Billett sandy loam, moderately well drained, 0 to 3 percent slopes	1.4	0.1%
BoE	Boone fine sand, 20 to 45 percent slopes	234.8	21.6%
Cb	Capitola-Cebana complex, 0 to 2 percent slopes, very stony	26.6	2.5%
CkC2	Chetek sandy loam, 6 to 12 percent slopes, eroded	0.9	0.1%
CkD2	Chetek-Mahtomedi complex, 12 to 25 percent slopes, eroded	2.6	0.2%
ElB	Eleva sandy loam, 2 to 6 percent slopes	34.3	3.2%
ElC2	Eleva sandy loam, 6 to 12 percent slopes, eroded	74.8	6.9%
ElD2	Eleva sandy loam, 12 to 20 percent slopes, eroded	12.3	1.1%
EmB	Elkmound loam, 2 to 6 percent slopes	3.4	0.3%
EmC2	Elkmound loam, 6 to 12 percent slopes, moderately eroded	1.2	0.1%
EmD2	Elkmound loam, 12 to 20 percent slopes, moderately eroded	62.8	5.8%
FnB	Freeon silt loam, 2 to 6 percent slopes	2.0	0.2%
GaB	Gale silt loam, 2 to 6 percent slopes	0.9	0.1%

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
GaC2	Gale silt loam, 6 to 12 percent slopes, eroded	9.1	0.8%
GaD2	Gale silt loam, 12 to 20 percent slopes, eroded	19.3	1.8%
HnB	Hixton loam, 2 to 6 percent slopes	43.8	4.0%
HnC2	Hixton loam, 6 to 12 percent slopes, eroded	22.7	2.1%
MbB	Magnor silt loam, 0 to 4 percent slopes	17.3	1.6%
MkC	Menahga loamy sand, 6 to 12 percent slopes	5.9	0.5%
MlB	Meridian loam, 2 to 6 percent slopes	107.3	9.9%
NtC2	Northfield silt loam, 6 to 12 percent slopes, eroded	8.5	0.8%
PdC	Plainbo loamy sand, 6 to 12 percent slopes	12.1	1.1%
PdD	Plainbo loamy sand, 12 to 20 percent slopes	115.8	10.7%
Px	Poskin silt loam, 0 to 2 percent slopes	4.0	0.4%
RoB	Rosholt sandy loam, 2 to 6 percent slopes	1.1	0.1%
SeB	Seaton silt loam, driftless valley, 2 to 6 percent slopes	18.1	1.7%
SeC2	Seaton silt loam, driftless valley, 6 to 12 percent slopes, moderately eroded	50.7	4.7%
SeD2	Seaton silt loam, driftless valley, 12 to 20 percent slopes, moderately eroded	31.2	2.9%
SfA	Seaton silt loam, moderately well drained, 0 to 3 percent slopes	17.9	1.7%
So	Shiffer loam, 0 to 2 percent slopes	15.1	1.4%
Totals for Area of Interest		**1,085.2**	**100.0%**

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic

class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Chippewa County, Wisconsin

AlC—Amery sandy loam, 6 to 12 percent slopes

Map Unit Setting

National map unit symbol: g4l3
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Amery, deep to dense layer, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Amery, Deep To Dense Layer

Setting

Landform: Moraines
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy drift over sandy loam till and/or loamy sand till

Typical profile

A - 0 to 2 inches: sandy loam
E - 2 to 11 inches: sandy loam
B/E - 11 to 22 inches: sandy loam
Bt1,Bt2 - 22 to 32 inches: sandy loam
C - 32 to 60 inches: sandy loam

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.14 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 4.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G090AY005WI)
Hydric soil rating: No

Minor Components

Cable

Percent of map unit:
Landform: Depressions

Hydric soil rating: Yes

AoA—Arenzville silt loam, 0 to 3 percent slopes, occasionally flooded

Map Unit Setting

National map unit symbol: 2wtqs
Elevation: 560 to 1,740 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: Prime farmland if protected from flooding or not frequently flooded during the growing season

Map Unit Composition

Arenzville, occassionally flooded, and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arenzville, Occassionally Flooded

Setting

Landform: Flood plains, drainageways
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope, talf, rise
Down-slope shape: Linear, convex
Across-slope shape: Linear
Parent material: Silty alluvium

Typical profile

A - 0 to 10 inches: silt loam
C - 10 to 25 inches: stratified silt loam
Ab - 25 to 40 inches: silt loam
C' - 40 to 79 inches: stratified silt loam to very fine sand

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Moderately well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.14 to 1.42 in/hr)
Depth to water table: About 48 to 72 inches
Frequency of flooding: Occasional
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very high (about 12.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: B

Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Minor Components

Orion, occassionally flooded
Percent of map unit: 3 percent
Landform: Flood plains, drainageways
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Talf
Down-slope shape: Linear
Across-slope shape: Linear
Other vegetative classification: High AWC, high water table (G105XY007WI)
Hydric soil rating: No

Ettrick, frequently flooded
Percent of map unit: 2 percent
Landform: Depressions on flood plains
Landform position (three-dimensional): Dip
Microfeatures of landform position: Swales
Down-slope shape: Concave, linear
Across-slope shape: Linear
Other vegetative classification: High AWC, high water table (G105XY007WI)
Hydric soil rating: Yes

ApB—Arland sandy loam, 2 to 6 percent slopes

Map Unit Setting
National map unit symbol: g4l9
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: All areas are prime farmland

Map Unit Composition
Arland and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arland

Setting
Landform: Hills
Landform position (two-dimensional): Summit
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy till over sandstone and/or sandy residuum

Typical profile
Ap - 0 to 7 inches: sandy loam
Bt1 - 7 to 11 inches: sandy loam

Bt2 - 11 to 25 inches: sandy loam
BC,2C - 25 to 35 inches: sandy loam
2Cr - 35 to 60 inches: bedrock

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: About 35 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI)
Hydric soil rating: No

ApC2—Arland sandy loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4lb
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Arland and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arland

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy till over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 7 inches: sandy loam
Bt1 - 7 to 11 inches: sandy loam
Bt2 - 11 to 25 inches: sandy loam
BC,2C - 25 to 35 inches: sandy loam
2Cr - 35 to 60 inches: bedrock

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: About 35 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI)
Hydric soil rating: No

ApD2—Arland sandy loam, 12 to 20 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4lc
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Not prime farmland

Map Unit Composition

Arland and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arland

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy till over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 7 inches: sandy loam
Bt1 - 7 to 11 inches: sandy loam
Bt2 - 11 to 25 inches: sandy loam
BC,2C - 25 to 35 inches: sandy loam
2Cr - 35 to 60 inches: bedrock

Properties and qualities

Slope: 12 to 20 percent
Depth to restrictive feature: About 35 inches to paralithic bedrock

Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.1 inches)

Interpretive groups
Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained with limitations (G105XY006WI)
Hydric soil rating: No

AsB—Arland loam, 2 to 6 percent slopes

Map Unit Setting
National map unit symbol: g4ld
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: All areas are prime farmland

Map Unit Composition
Arland and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arland

Setting
Landform: Hills
Landform position (two-dimensional): Summit
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy till over sandstone and/or sandy residuum

Typical profile
Ap - 0 to 7 inches: loam
Bt1 - 7 to 11 inches: sandy loam
Bt2 - 11 to 25 inches: sandy loam
BC,2C - 25 to 35 inches: sandy loam
2Cr - 35 to 60 inches: bedrock

Properties and qualities
Slope: 2 to 6 percent
Depth to restrictive feature: About 35 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI)
Hydric soil rating: No

BIB—Billett sandy loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: g4ln
Elevation: 400 to 1,500 feet
Mean annual precipitation: 25 to 40 inches
Mean annual air temperature: 39 to 57 degrees F
Frost-free period: 130 to 190 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Billett and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Billett

Setting

Landform: Outwash plains
Landform position (two-dimensional): Summit
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy drift over sandy outwash

Typical profile

Ap - 0 to 9 inches: sandy loam
E,BE,Bt - 9 to 30 inches: sandy loam
BC - 30 to 36 inches: loamy sand
C1,C2 - 36 to 60 inches: loamy sand

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None

Frequency of ponding: None
Calcium carbonate, maximum in profile: 20 percent
Available water storage in profile: Moderate (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3s
Hydrologic Soil Group: A
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

BIC2—Billett sandy loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4lp
Elevation: 400 to 1,500 feet
Mean annual precipitation: 25 to 40 inches
Mean annual air temperature: 39 to 57 degrees F
Frost-free period: 130 to 190 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Billett and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Billett

Setting

Landform: Outwash plains
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy drift over sandy outwash

Typical profile

Ap - 0 to 9 inches: sandy loam
E,BE,Bt - 9 to 30 inches: sandy loam
BC - 30 to 36 inches: loamy sand
C1,C2 - 36 to 60 inches: loamy sand

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 20 percent
Available water storage in profile: Moderate (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: A
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

BmA—Billett sandy loam, moderately well drained, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: g4lq
Elevation: 680 to 1,700 feet
Mean annual precipitation: 25 to 35 inches
Mean annual air temperature: 39 to 50 degrees F
Frost-free period: 130 to 170 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Billett, moderately well drained, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Billett, Moderately Well Drained

Setting

Landform: Outwash plains
Landform position (two-dimensional): Summit
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Loamy drift over sandy outwash

Typical profile

Ap - 0 to 8 inches: sandy loam
E,BE,Bt,BC - 8 to 37 inches: fine sandy loam
C1,C2 - 37 to 60 inches: fine sand

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Moderately well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 20 percent
Available water storage in profile: Moderate (about 6.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3s
Hydrologic Soil Group: A

Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

BoE—Boone fine sand, 20 to 45 percent slopes

Map Unit Setting

National map unit symbol: g4lr
Elevation: 700 to 1,400 feet
Mean annual precipitation: 28 to 35 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 135 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Boone and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Boone

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Sandy residuum over sandstone

Typical profile

A - 0 to 2 inches: fine sand
C1,C2,C3 - 2 to 22 inches: fine sand
Cr - 22 to 60 inches: bedrock

Properties and qualities

Slope: 20 to 45 percent
Depth to restrictive feature: About 22 inches to paralithic bedrock
Natural drainage class: Excessively drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Very low (about 1.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: A
Other vegetative classification: Low AWC, adequately drained with limitations (G105XY003WI)
Hydric soil rating: No

Cb—Capitola-Cebana complex, 0 to 2 percent slopes, very stony

Map Unit Setting

National map unit symbol: 2tnyq
Elevation: 920 to 1,770 feet
Mean annual precipitation: 27 to 36 inches
Mean annual air temperature: 37 to 46 degrees F
Frost-free period: 80 to 150 days
Farmland classification: Prime farmland if drained

Map Unit Composition

Capitola, very stony, and similar soils: 40 percent
Cebana, very stony, and similar soils: 30 percent
Minor components: 30 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Capitola, Very Stony

Setting

Landform: Depressions on ground moraines, drainageways on ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave, linear
Across-slope shape: Concave
Parent material: Silty alluvium and/or loamy alluvium over dense sandy loam till

Typical profile

Oa - 0 to 5 inches: muck
A - 5 to 7 inches: silt loam
Bg - 7 to 22 inches: silt loam
2Btg - 22 to 33 inches: sandy loam
2Cd - 33 to 79 inches: sandy loam

Properties and qualities

Slope: 0 to 2 percent
Percent of area covered with surface fragments: 1.5 percent
Depth to restrictive feature: 20 to 39 inches to densic material
Natural drainage class: Very poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low (0.01 to 0.06 in/hr)
Depth to water table: About 0 inches
Frequency of flooding: None
Frequency of ponding: Frequent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Moderate (about 6.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7w
Hydrologic Soil Group: C/D

Other vegetative classification: Mod AWC, high water table (G090AY004WI), Not Assigned (wet mineral soils) (Nmin)
Hydric soil rating: Yes

Description of Cebana, Very Stony

Setting
Landform: Ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Silty loess and/or silty lacustrine deposits over dense loamy till

Typical profile
A - 0 to 5 inches: silt loam
Eg - 5 to 13 inches: silt loam
E/B - 13 to 27 inches: silt loam
2Bt - 27 to 49 inches: loam
2BCd - 49 to 67 inches: sandy loam
2Cd - 67 to 79 inches: sandy loam

Properties and qualities
Slope: 0 to 2 percent
Percent of area covered with surface fragments: 1.5 percent
Depth to restrictive feature: 39 to 59 inches to densic material
Natural drainage class: Poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low (0.01 to 0.06 in/hr)
Depth to water table: About 0 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Moderate (about 7.9 inches)

Interpretive groups
Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6w
Hydrologic Soil Group: C/D
Other vegetative classification: High AWC, high water table (G090AY007WI)
Hydric soil rating: Yes

Minor Components

Magnor, very stony
Percent of map unit: 10 percent
Landform: Ground moraines
Landform position (three-dimensional): Talf
Down-slope shape: Linear
Across-slope shape: Linear
Other vegetative classification: Mod AWC, high water table (G090AY004WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Viburnum (AVb), Acer saccharum/Hydrophyllum (AH), Acer saccarum/Hydrophyllum=(Circaea) (AH-Ci), Acer saccharum-Tsuga/ Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO), Tsuga/ Maianthemum-Coptis (TMC)
Hydric soil rating: No

Cathro

Percent of map unit: 10 percent
Landform: Depressions on ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Auburndale, very stony

Percent of map unit: 5 percent
Landform: Ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Other vegetative classification: High AWC, high water table (G090AY007WI), Not Assigned (wet mineral soils) (Nmin)
Hydric soil rating: Yes

Capitola, very stony, briefly flooded

Percent of map unit: 3 percent
Landform: Drainageways on ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Linear
Across-slope shape: Concave
Other vegetative classification: Mod AWC, high water table (G090AY004WI), Not Assigned (wet mineral soils) (Nmin)
Hydric soil rating: Yes

Cebana, very stony, briefly flooded

Percent of map unit: 2 percent
Landform: Ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Linear
Across-slope shape: Concave
Other vegetative classification: High AWC, high water table (G090AY007WI)
Hydric soil rating: Yes

CkC2—Chetek sandy loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4m2
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Not prime farmland

Map Unit Composition

Chetek and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chetek

Setting

Landform: End moraines, outwash plains, stream terraces
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Riser
Down-slope shape: Convex
Across-slope shape: Convex

Typical profile

Ap - 0 to 8 inches: sandy loam
E - 8 to 13 inches: sandy loam
Bt1 - 13 to 17 inches: gravelly loamy sand
2Bt2,2C - 17 to 60 inches: stratified coarse sand to sand

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Somewhat excessively drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 3.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: B
Other vegetative classification: Low AWC, adequately drained (G090BY002WI)
Hydric soil rating: No

CkD2—Chetek-Mahtomedi complex, 12 to 25 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4m3
Elevation: 670 to 1,950 feet
Mean annual precipitation: 22 to 33 inches
Mean annual air temperature: 36 to 45 degrees F
Frost-free period: 88 to 142 days
Farmland classification: Not prime farmland

Map Unit Composition

Chetek and similar soils: 55 percent
Mahtomedi and similar soils: 45 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chetek

Setting

Landform: End moraines, outwash plains
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Thin loamy drift over stratified sandy and gravelly outwash

Typical profile

Ap - 0 to 8 inches: sandy loam
E - 8 to 13 inches: sandy loam
Bt1 - 13 to 17 inches: gravelly loamy sand
2Bt2,2C - 17 to 60 inches: stratified coarse sand to sand

Properties and qualities

Slope: 12 to 25 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Somewhat excessively drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 3.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: B
Other vegetative classification: Low AWC, adequately drained with limitations (G105XY003WI)
Hydric soil rating: No

Description of Mahtomedi

Setting

Landform: End moraines, outwash plains
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Sandy and gravelly outwash

Typical profile

Ap - 0 to 8 inches: loamy sand
Bw1 - 8 to 18 inches: sand
Bw2 - 18 to 24 inches: gravelly sand
C - 24 to 60 inches: sand

Properties and qualities

Slope: 12 to 25 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Excessively drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)

Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 15 percent
Available water storage in profile: Low (about 4.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: A
Other vegetative classification: Low AWC, adequately drained with limitations (G105XY003WI)
Hydric soil rating: No

ElB—Eleva sandy loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: g4m7
Elevation: 680 to 1,360 feet
Mean annual precipitation: 28 to 35 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 140 to 190 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Eleva and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Eleva

Setting

Landform: Hills
Landform position (two-dimensional): Summit, footslope
Down-slope shape: Convex, linear
Across-slope shape: Convex, concave
Parent material: Loamy drift over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 9 inches: sandy loam
BA,Bt1,Bt2 - 9 to 36 inches: sandy loam
C - 36 to 40 inches: sand
Cr - 40 to 60 inches: bedrock

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: About 40 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 5.95 in/hr)
Depth to water table: More than 80 inches

Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3s
Hydrologic Soil Group: A
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

EIC2—Eleva sandy loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4m8
Elevation: 680 to 1,360 feet
Mean annual precipitation: 28 to 35 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 140 to 190 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Eleva and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Eleva

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy drift over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 9 inches: sandy loam
BA,Bt1,Bt2 - 9 to 36 inches: sandy loam
C - 36 to 40 inches: sand
Cr - 40 to 60 inches: bedrock

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: About 40 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: A
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

EID2—Eleva sandy loam, 12 to 20 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4m9
Elevation: 680 to 1,360 feet
Mean annual precipitation: 28 to 35 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 140 to 190 days
Farmland classification: Not prime farmland

Map Unit Composition

Eleva and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Eleva

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy drift over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 9 inches: sandy loam
BA,Bt1,Bt2 - 9 to 36 inches: sandy loam
C - 36 to 40 inches: sand
Cr - 40 to 60 inches: bedrock

Properties and qualities

Slope: 12 to 20 percent
Depth to restrictive feature: About 40 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: A

Other vegetative classification: Mod AWC, adequately drained with limitations (G105XY006WI)
Hydric soil rating: No

EmB—Elkmound loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: 2tc6f
Elevation: 560 to 1,740 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Elkmound and similar soils: 93 percent
Minor components: 7 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Elkmound

Setting

Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy slope alluvium over loamy residuum weathered from sandstone

Typical profile

Ap - 0 to 6 inches: loam
2Bw - 6 to 12 inches: channery loam
2Cr - 12 to 79 inches: bedrock

Properties and qualities

Slope: 2 to 6 percent
Percent of area covered with surface fragments: 1.0 percent
Depth to restrictive feature: 12 to 20 inches to paralithic bedrock
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.20 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very low (about 2.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3s

Hydrologic Soil Group: D
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

Minor Components

Hixton, thin solum
Percent of map unit: 4 percent
Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

Elevasil
Percent of map unit: 2 percent
Landform: Ridges
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

Boone
Percent of map unit: 1 percent
Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

EmC2—Elkmound loam, 6 to 12 percent slopes, moderately eroded

Map Unit Setting
National map unit symbol: 2tc6g
Elevation: 560 to 1,740 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: Not prime farmland

Map Unit Composition
Elkmound, moderately eroded, and similar soils: 93 percent
Minor components: 7 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Elkmound, Moderately Eroded

Setting

Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy slope alluvium over loamy residuum weathered from sandstone

Typical profile

Ap - 0 to 6 inches: loam
2Bw - 6 to 12 inches: channery loam
2Cr - 12 to 79 inches: bedrock

Properties and qualities

Slope: 6 to 12 percent
Percent of area covered with surface fragments: 1.0 percent
Depth to restrictive feature: 12 to 20 inches to paralithic bedrock
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.20 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very low (about 2.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4s
Hydrologic Soil Group: D
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

Minor Components

Hixton, thin solum

Percent of map unit: 4 percent
Landform: Ridges
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

Elevasil, moderately eroded

Percent of map unit: 2 percent
Landform: Ridges
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Linear

Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

Boone

Percent of map unit: 1 percent
Landform: Ridges
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

EmD2—Elkmound loam, 12 to 20 percent slopes, moderately eroded

Map Unit Setting

National map unit symbol: 2tc6h
Elevation: 560 to 1,740 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: Not prime farmland

Map Unit Composition

Elkmound, moderately eroded, and similar soils: 94 percent
Minor components: 6 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Elkmound, Moderately Eroded

Setting

Landform: Valley sides
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy slope alluvium over loamy residuum weathered from sandstone

Typical profile

Ap - 0 to 6 inches: loam
2Bw - 6 to 12 inches: channery loam
2Cr - 12 to 79 inches: bedrock

Properties and qualities

Slope: 12 to 20 percent
Percent of area covered with surface fragments: 1.0 percent
Depth to restrictive feature: 12 to 20 inches to paralithic bedrock
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.20 to 1.98 in/hr)

Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very low (about 2.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: D
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

Minor Components

Hixton, thin solum

Percent of map unit: 4 percent
Landform: Valley sides
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

Elevasil, moderately eroded

Percent of map unit: 2 percent
Landform: Valley sides
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

FnB—Freeon silt loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: 2tnym
Elevation: 840 to 1,700 feet
Mean annual precipitation: 28 to 36 inches
Mean annual air temperature: 39 to 48 degrees F
Frost-free period: 120 to 170 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Freeon and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Freeon

Setting

Landform: Ground moraines, moraines
Landform position (two-dimensional): Summit, backslope, shoulder
Landform position (three-dimensional): Interfluve, rise
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loess and/or silty lacustrine deposits over dense sandy loam till

Typical profile

Ap - 0 to 8 inches: silt loam
E - 8 to 13 inches: silt loam
E/B - 13 to 19 inches: silt loam
2B/E - 19 to 26 inches: sandy loam
2Bt - 26 to 45 inches: sandy loam
2BCd - 45 to 58 inches: sandy loam
2Cd - 58 to 79 inches: sandy loam

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: 39 to 59 inches to densic material
Natural drainage class: Moderately well drained
Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low (0.01 to 0.06 in/hr)
Depth to water table: About 6 to 18 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Moderate (about 7.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C/D
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Hydrophyllum (AH), Acer saccharum-Tsuga/Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO)
Hydric soil rating: No

Minor Components

Magnor

Percent of map unit: 10 percent
Landform: Ground moraines, moraines
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope, talf
Down-slope shape: Linear, concave
Across-slope shape: Linear
Other vegetative classification: Mod AWC, high water table (G090BY004WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Viburnum (AVb), Acer saccharum/Hydrophyllum (AH), Acer saccarum/Hydrophyllum=(Circaea) (AH-Ci), Acer saccharum-Tsuga/

Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO), Tsuga/ Maianthemum-Coptis (TMC)
Hydric soil rating: No

Santiago
Percent of map unit: 3 percent
Landform: Ground moraines, moraines
Landform position (two-dimensional): Shoulder, backslope
Landform position (three-dimensional): Side slope, rise
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: High AWC, adequately drained with limitations (G090BY009WI), Acer saccharum/Athyrium (AAt), Acer saccharum/ Caulophyllum-Circaea (ACaCi)
Hydric soil rating: No

Capitola
Percent of map unit: 3 percent
Landform: Depressions on ground moraines, drainageways on ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave, linear
Across-slope shape: Concave
Other vegetative classification: Mod AWC, high water table (G090BY004WI), Not Assigned (wet mineral soils) (Nmin)
Hydric soil rating: Yes

Haugen
Percent of map unit: 2 percent
Landform: Moraines
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI), Acer saccharum/Vaccinium-Desmodium (AVDe), Acer saccharum/Athyrium (AAt)
Hydric soil rating: No

Freeon, very stony
Percent of map unit: 2 percent
Landform: Ground moraines, moraines
Landform position (two-dimensional): Summit, backslope, shoulder
Landform position (three-dimensional): Interfluve, rise
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Hydrophyllum (AH), Acer saccharum-Tsuga/ Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO)
Hydric soil rating: No

GaB—Gale silt loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: g4mq
Elevation: 700 to 1,400 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Gale and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Gale

Setting

Landform: Hills
Landform position (two-dimensional): Summit
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Silty drift over thin sandy residuum over sandstone

Typical profile

Ap - 0 to 8 inches: silt loam
E,BE,Bt - 8 to 30 inches: silt loam
2BC - 30 to 36 inches: sand
2Cr,2R - 36 to 60 inches: weathered bedrock

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: About 36 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Moderate (about 6.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

GaC2—Gale silt loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4mr
Elevation: 700 to 1,400 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 160 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Gale and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Gale

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Silty drift over thin sandy residuum over sandstone

Typical profile

Ap - 0 to 8 inches: silt loam
E,BE,Bt - 8 to 30 inches: silt loam
2BC - 30 to 36 inches: sand
2Cr,2R - 36 to 60 inches: weathered bedrock

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: About 36 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Moderate (about 6.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

GaD2—Gale silt loam, 12 to 20 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4ms
Elevation: 700 to 1,400 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Gale and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Gale

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Silty drift over thin sandy residuum over sandstone

Typical profile

Ap - 0 to 8 inches: silt loam
E,BE,Bt - 8 to 30 inches: silt loam
2BC - 30 to 36 inches: sand
2Cr,2R - 36 to 60 inches: weathered bedrock

Properties and qualities

Slope: 12 to 20 percent
Depth to restrictive feature: About 36 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Moderate (about 6.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained with limitations (G105XY006WI)
Hydric soil rating: No

HnB—Hixton loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: g4my
Elevation: 800 to 1,400 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Hixton and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hixton

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, footslope
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Loamy drift over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 7 inches: loam
E,Bt,BC - 7 to 24 inches: loam
2C - 24 to 34 inches: sand
2R - 34 to 38 inches: bedrock

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: 20 to 40 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

HnC2—Hixton loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4mz
Elevation: 800 to 1,400 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 160 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Hixton and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hixton

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy drift over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 7 inches: loam
E,Bt,BC - 7 to 24 inches: loam
2C - 24 to 34 inches: sand
2R - 34 to 38 inches: bedrock

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: 20 to 40 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 5.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: C
Other vegetative classification: Mod AWC, adequately drained (G105XY005WI)
Hydric soil rating: No

MbB—Magnor silt loam, 0 to 4 percent slopes

Map Unit Setting

National map unit symbol: 2tnyj
Elevation: 900 to 1,690 feet
Mean annual precipitation: 28 to 36 inches
Mean annual air temperature: 39 to 48 degrees F
Frost-free period: 120 to 170 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Magnor and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Magnor

Setting

Landform: Drumlins, ground moraines, moraines
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope, talf
Down-slope shape: Concave, linear
Across-slope shape: Linear
Parent material: Loess and/or silty lacustrine deposits over dense sandy loam till

Typical profile

Ap - 0 to 10 inches: silt loam
E - 10 to 14 inches: silt loam
E/B - 14 to 17 inches: silt loam
B/E - 17 to 24 inches: silt loam
2Bt1 - 24 to 35 inches: sandy loam
2Bt2 - 35 to 44 inches: sandy loam
2BCd - 44 to 56 inches: sandy loam
2Cd - 56 to 79 inches: sandy loam

Properties and qualities

Slope: 0 to 4 percent
Depth to restrictive feature: 39 to 59 inches to densic material
Natural drainage class: Somewhat poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low (0.01 to 0.06 in/hr)
Depth to water table: About 4 to 12 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Moderate (about 7.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w

Hydrologic Soil Group: C/D
Other vegetative classification: Mod AWC, high water table (G090BY004WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Viburnum (AVb), Acer saccharum/Hydrophyllum (AH), Acer saccarum/Hydrophyllum=(Circaea) (AH-Ci), Acer saccharum-Tsuga/Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO), Tsuga/Maianthemum-Coptis (TMC)
Hydric soil rating: No

Minor Components

Freeon
Percent of map unit: 8 percent
Landform: Drumlins, ground moraines, moraines
Landform position (two-dimensional): Footslope, summit, shoulder, backslope
Landform position (three-dimensional): Base slope, interfluve, rise
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Hydrophyllum (AH), Acer saccharum-Tsuga/Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO)
Hydric soil rating: No

Cebana
Percent of map unit: 4 percent
Landform: Ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Other vegetative classification: High AWC, high water table (G090AY007WI)
Hydric soil rating: Yes

Capitola
Percent of map unit: 2 percent
Landform: Depressions on ground moraines, drainageways on ground moraines
Landform position (three-dimensional): Dip
Down-slope shape: Concave, linear
Across-slope shape: Concave
Other vegetative classification: Mod AWC, high water table (G090BY004WI), Not Assigned (wet mineral soils) (Nmin)
Hydric soil rating: Yes

Pesabic
Percent of map unit: 2 percent
Landform: Moraines
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Linear
Other vegetative classification: Mod AWC, high water table (G090AY004WI), Acer saccharum-Tsuga/Maianthemum (ATM), Tsuga/Maianthemum-Coptis (TMC)
Hydric soil rating: No

Almena
Percent of map unit: 2 percent
Landform: Ground moraines

Landform position (three-dimensional): Talf
Down-slope shape: Linear
Across-slope shape: Linear
Other vegetative classification: High AWC, high water table (G090BY007WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccarum/Hydrophyllum=(Circaea) (AH-Ci)
Hydric soil rating: No

Magnor, very stony

Percent of map unit: 2 percent
Landform: Drumlins, ground moraines, moraines
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope, talf
Down-slope shape: Concave, linear
Across-slope shape: Linear
Other vegetative classification: Mod AWC, high water table (G090BY004WI), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum/Viburnum (AVb), Acer saccharum/Hydrophyllum (AH), Acer saccarum/Hydrophyllum=(Circaea) (AH-Ci), Acer saccharum-Tsuga/Maianthemum (ATM), Acer saccharum/Viola-Osmorhiza (AViO), Tsuga/Maianthemum-Coptis (TMC)
Hydric soil rating: No

MkC—Menahga loamy sand, 6 to 12 percent slopes

Map Unit Setting

National map unit symbol: g4ng
Elevation: 670 to 1,600 feet
Mean annual precipitation: 22 to 33 inches
Mean annual air temperature: 36 to 45 degrees F
Frost-free period: 88 to 150 days
Farmland classification: Not prime farmland

Map Unit Composition

Menahga and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Menahga

Setting

Landform: Outwash plains
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Convex
Parent material: Sandy outwash

Typical profile

Ap - 0 to 8 inches: loamy sand

Bw1 - 8 to 15 inches: coarse sand
Bw2 - 15 to 40 inches: coarse sand
C - 40 to 60 inches: coarse sand

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 4.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: A
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

Minor Components

Plainbo

Percent of map unit: 5 percent
Landform: Outwash plains
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Convex
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

MIB—Meridian loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: g4nj
Elevation: 680 to 1,950 feet
Mean annual precipitation: 28 to 35 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 120 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Meridian and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Meridian

Setting

Landform: Stream terraces
Landform position (three-dimensional): Tread
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Loamy alluvium over sandy outwash

Typical profile

Ap - 0 to 9 inches: loam
E - 9 to 11 inches: loam
Bt1,Bt2 - 11 to 37 inches: loam
2C - 37 to 60 inches: sand

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Moderate (about 8.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: B
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

NtC2—Northfield silt loam, 6 to 12 percent slopes, eroded

Map Unit Setting

National map unit symbol: g4nr
Elevation: 800 to 1,400 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Northfield and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Northfield

Setting

Landform: Hills

Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Thin silty drift over sandstone and/or sandy residuum

Typical profile

Ap - 0 to 8 inches: silt loam
E,Bt1,Bt2 - 8 to 18 inches: loam
2R - 18 to 22 inches: bedrock

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: 10 to 20 inches to paralithic bedrock
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Low (about 3.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: D
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

PdC—Plainbo loamy sand, 6 to 12 percent slopes

Map Unit Setting

National map unit symbol: g4nz
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Not prime farmland

Map Unit Composition

Plainbo and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Plainbo

Setting

Landform: Hills
Landform position (two-dimensional): Footslope
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Sandy drift over sandstone

Typical profile

Ap - 0 to 6 inches: loamy sand
Bw,BC - 6 to 20 inches: sand
C - 20 to 28 inches: sand
2Cr - 28 to 60 inches: bedrock

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: About 28 inches to paralithic bedrock
Natural drainage class: Excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Very low to high (0.00 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Very low (about 2.2 inches)

Interpretive groups

Land capability classification (irrigated): 4e
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: A
Other vegetative classification: Low AWC, adequately drained (G105XY002WI)
Hydric soil rating: No

PdD—Plainbo loamy sand, 12 to 20 percent slopes

Map Unit Setting

National map unit symbol: g4p0
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Not prime farmland

Map Unit Composition

Plainbo and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Plainbo

Setting

Landform: Hills
Landform position (two-dimensional): Shoulder, backslope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Sandy drift over sandstone

Typical profile

Ap - 0 to 6 inches: loamy sand
Bw,BC - 6 to 20 inches: sand
C - 20 to 28 inches: sand

2Cr - 28 to 60 inches: bedrock

Properties and qualities

Slope: 12 to 20 percent
Depth to restrictive feature: About 28 inches to paralithic bedrock
Natural drainage class: Excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Very low to high (0.00 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Very low (about 2.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: A
Other vegetative classification: Low AWC, adequately drained with limitations (G105XY003WI)
Hydric soil rating: No

Px—Poskin silt loam, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: g4p2
Elevation: 800 to 1,950 feet
Mean annual precipitation: 28 to 33 inches
Mean annual air temperature: 39 to 45 degrees F
Frost-free period: 120 to 135 days
Farmland classification: Prime farmland if drained

Map Unit Composition

Poskin and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Poskin

Setting

Landform: Depressions on stream terraces, depressions on outwash plains
Landform position (two-dimensional): Footslope
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Loamy drift and/or silty drift over sandy and gravelly outwash

Typical profile

Ap - 0 to 10 inches: silt loam
E - 10 to 14 inches: silt loam
E/B,B/E - 14 to 23 inches: silt loam
Bt1 - 23 to 29 inches: silt loam
2Bt2 - 29 to 38 inches: sandy loam
2C - 38 to 60 inches: Error

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Somewhat poorly drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: About 6 inches
Frequency of flooding: None
Frequency of ponding: None
Available water storage in profile: Moderate (about 8.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: B/D
Other vegetative classification: High AWC, high water table (G090AY007WI)
Hydric soil rating: No

Minor Components

Rib

Percent of map unit:
Landform: Depressions
Hydric soil rating: Yes

RoB—Rosholt sandy loam, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: 2tnzd
Elevation: 690 to 1,460 feet
Mean annual precipitation: 27 to 36 inches
Mean annual air temperature: 37 to 46 degrees F
Frost-free period: 80 to 150 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Rosholt and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Rosholt

Setting

Landform: Terraces, flats, hillslopes
Landform position (two-dimensional): Summit, shoulder, backslope
Landform position (three-dimensional): Interfluve, side slope, riser, rise
Down-slope shape: Convex
Across-slope shape: Convex

Parent material: Loamy glaciofluvial deposits over stratified sandy and gravelly outwash

Typical profile

Ap - 0 to 8 inches: sandy loam
E - 8 to 13 inches: sandy loam
B/E - 13 to 20 inches: sandy loam
Bt1 - 20 to 28 inches: sandy loam
2Bt2 - 28 to 34 inches: gravelly loamy sand
2C - 34 to 79 inches: stratified sand to very gravelly coarse sand

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.60 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Low (about 4.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: A
Other vegetative classification: Mod AWC, adequately drained (G090AY005WI), Acer saccharum/Vaccinium-Desmodium (AVDe), Acer saccharum/Athyrium (AAt), Acer saccharum/Caulophyllum-Circaea (ACaCi), Acer saccharum-Quercus/Viburnum=(Vaccinium) (AQVb-V)
Hydric soil rating: No

Minor Components

Scott lake

Percent of map unit: 10 percent
Landform: Terraces, flats, hillslopes
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope, tread, rise
Down-slope shape: Linear
Across-slope shape: Linear
Other vegetative classification: Mod AWC, adequately drained (G090AY005WI), Acer saccharum/Hydrophyllum (AH), Acer saccharum/Viola-Osmorhiza (AViO)
Hydric soil rating: No

Antigo

Percent of map unit: 5 percent
Landform: Terraces, flats, hillslopes
Landform position (two-dimensional): Shoulder, backslope, summit
Landform position (three-dimensional): Interfluve, side slope, riser, rise
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: Mod AWC, adequately drained (G090BY005WI), Acer saccharum/Hydrophyllum (AH), Acer saccharum/Viola-Osmorhiza (AViO)
Hydric soil rating: No

Chetek

Percent of map unit: 3 percent
Landform: Terraces, flats, hillslopes
Landform position (two-dimensional): Summit, shoulder, backslope
Landform position (three-dimensional): Interfluve, side slope, riser, rise
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: Low AWC, adequately drained (G090AY002WI), Acer saccharum/Vaccinium-Desmodium (AVDe), Acer saccharum/Athyrium (AAt), Pinus strobus/Amphicarpa bracteata (PAm)
Hydric soil rating: No

Cress

Percent of map unit: 2 percent
Landform: Terraces, flats, hillslopes
Landform position (two-dimensional): Summit, shoulder, backslope
Landform position (three-dimensional): Interfluve, side slope, riser, rise
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: Low AWC, adequately drained (G090AY002WI), Acer saccharum/Vaccinium-Desmodium (AVDe), Pinus strobus/Amphicarpa bracteata (PAm)
Hydric soil rating: No

SeB—Seaton silt loam, driftless valley, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: 2v3f2
Elevation: 800 to 1,400 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Seaton and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Seaton

Setting

Landform: Knolls
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Loess

Typical profile

Ap - 0 to 9 inches: silt loam
BE - 9 to 15 inches: silt loam
Bt1 - 15 to 21 inches: silt loam
Bt2 - 21 to 27 inches: silt loam
Bt3 - 27 to 34 inches: silt loam
Bt4 - 34 to 44 inches: silt loam
BC - 44 to 70 inches: silt loam
C - 70 to 79 inches: silt loam

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very high (about 12.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: B
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Minor Components

Council

Percent of map unit: 2 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Head slope
Down-slope shape: Concave
Across-slope shape: Linear
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Greenridge

Percent of map unit: 1 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Lambeau

Percent of map unit: 1 percent
Landform: Knolls
Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Barremills

Percent of map unit: 1 percent
Landform: Knolls
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Interfluve
Down-slope shape: Concave
Across-slope shape: Concave
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

SeC2—Seaton silt loam, driftless valley, 6 to 12 percent slopes, moderately eroded

Map Unit Setting

National map unit symbol: 2v3fl
Elevation: 800 to 1,400 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Seaton and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Seaton

Setting

Landform: Knolls
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Loess

Typical profile

Ap - 0 to 9 inches: silt loam
BE - 9 to 15 inches: silt loam
Bt1 - 15 to 21 inches: silt loam
Bt2 - 21 to 27 inches: silt loam
Bt3 - 27 to 34 inches: silt loam
Bt4 - 34 to 44 inches: silt loam
BC - 44 to 70 inches: silt loam

C - 70 to 79 inches: silt loam

Properties and qualities

Slope: 6 to 12 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very high (about 12.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: B
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Minor Components

Council

Percent of map unit: 2 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Head slope
Down-slope shape: Concave
Across-slope shape: Concave
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Greenridge

Percent of map unit: 2 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

Lambeau

Percent of map unit: 1 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

SeD2—Seaton silt loam, driftless valley, 12 to 20 percent slopes, moderately eroded

Map Unit Setting

National map unit symbol: 2v3fm
Elevation: 800 to 1,400 feet
Mean annual precipitation: 31 to 39 inches
Mean annual air temperature: 41 to 50 degrees F
Frost-free period: 120 to 190 days
Farmland classification: Not prime farmland

Map Unit Composition

Seaton and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Seaton

Setting

Landform: Knolls
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Loess

Typical profile

Ap - 0 to 9 inches: silt loam
BE - 9 to 15 inches: silt loam
Bt1 - 15 to 21 inches: silt loam
Bt2 - 21 to 27 inches: silt loam
Bt3 - 27 to 34 inches: silt loam
Bt4 - 34 to 44 inches: silt loam
BC - 44 to 70 inches: silt loam
C - 70 to 79 inches: silt loam

Properties and qualities

Slope: 12 to 20 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very high (about 12.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: B
Other vegetative classification: High AWC, adequately drained with limitations (G105XY009WI)
Hydric soil rating: No

Minor Components

Council

Percent of map unit: 2 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Head slope
Down-slope shape: Concave
Across-slope shape: Concave
Other vegetative classification: High AWC, adequately drained with limitations (G105XY009WI)
Hydric soil rating: No

Greenridge

Percent of map unit: 2 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Other vegetative classification: High AWC, adequately drained with limitations (G105XY009WI)
Hydric soil rating: No

Lambeau

Percent of map unit: 1 percent
Landform: Knolls
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Other vegetative classification: High AWC, adequately drained with limitations (G105XY009WI)
Hydric soil rating: No

SfA—Seaton silt loam, moderately well drained, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: g4pp
Elevation: 680 to 1,700 feet
Mean annual precipitation: 25 to 35 inches
Mean annual air temperature: 39 to 50 degrees F

Frost-free period: 120 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition
Seaton, moderately well drained, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Seaton, Moderately Well Drained

Setting
Landform: Hills
Landform position (two-dimensional): Summit
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Silty loess

Typical profile
Ap - 0 to 9 inches: silt loam
E,Bt1,2,3 - 9 to 42 inches: silt loam
C - 42 to 60 inches: silt loam

Properties and qualities
Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Moderately well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 25 percent
Available water storage in profile: Very high (about 12.7 inches)

Interpretive groups
Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 1
Hydrologic Soil Group: B
Other vegetative classification: High AWC, adequately drained (G105XY008WI)
Hydric soil rating: No

So—Shiffer loam, 0 to 2 percent slopes

Map Unit Setting
National map unit symbol: g4pt
Elevation: 680 to 1,360 feet
Mean annual precipitation: 29 to 35 inches
Mean annual air temperature: 45 to 50 degrees F
Frost-free period: 140 to 160 days
Farmland classification: Prime farmland if drained

Map Unit Composition

Shiffer and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Shiffer

Setting

Landform: Depressions on stream terraces, drainageways on valley floors
Landform position (two-dimensional): Toeslope
Down-slope shape: Concave, linear
Across-slope shape: Concave

Typical profile

Ap - 0 to 9 inches: loam
Bt1,Bt2 - 9 to 27 inches: loam
2BC - 27 to 31 inches: sandy loam
2C - 31 to 60 inches: sand

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Somewhat poorly drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: About 12 to 36 inches
Frequency of flooding: Rare
Frequency of ponding: None
Available water storage in profile: Moderate (about 7.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: B/D
Other vegetative classification: Mod AWC, high water table (G090BY004WI)
Hydric soil rating: No

Minor Components

Lows

Percent of map unit:
Landform: Depressions
Hydric soil rating: Yes

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf